



4th house – 92.1m² + 42.9m² terrace.

1. Foundation. (optional)

Screw piles, SIP floor (SIP224) + terrace = EUR 8910.

Strip concrete foundation with subfloor = EUR 9700.

Insulated concrete slab = EUR 11300.

2. House frame.

External walls of SIP panels 224mm (insulation 200mm, EPS80)

Roof covering 224mm (insulation 200mm, EPS80)

Price of the industrially produced set at the factory (without floor) = EUR 27420.

Assembly of the set on the site = EUR 5490.

3. Windows. (optional)

PVC windows, double-glazed windows = EUR 4420.

PVC windows, triple-glazed windows = EUR 5130.

Assembly of the windows on the site = EUR 610.

4. Facade, terrace (heat-treated wood)

Heat-treated pine; finishing board 20x140 mm C6 profile; Natur class (with branches) = EUR 1660.

Terrace heat-treated pine; terrace board 26x115 mm D30sg profile; Natur class (with branches) = EUR 2040.

Assembly of the facade and terrace (heat-treated wood) on the site = EUR 2300.

5. Roof covering, facade RUUKKI

Standing seam metal roofing (Valcprofil A) Ruukki 50 Plus matt SR27-545A 0.50mm RR23 + gutters = EUR 5720.

Assembly of standing seam metal roofing (Valcprofil A) Ruukki 50 Plus matt SR27-545A 0.50mm RR23 + gutters on the site = EUR 4970.

6. Transport costs

Depending on the location of the site EUR 300-800.

The prices are given without interior decoration.

ALL PRICES ARE SPECIFIED EXCLUDING THE VAT.

The prices may change due to fluctuations in raw material prices.

CONTACT

“SIPpanel” Ltd.

Phone: +371 24115577

Email: sipmaja@sipmaja.lv

COMPANY DETAILS

“SIPpanel” Ltd.

VAT registration No.: LV41203070798

Address: 18-35 Zvejnieku Street, Roja, Roja county, LV-3264, Latvia

Address: 66C Augszemes Street, Akniste, Akniste county, LV-5208, Latvia