



7th house – 121.3m² + 40.8m² terrace + 30.7m² carport.

1. Foundation. (optional)

Concrete strip foundation with subfloor = EUR 8500.

Insulated concrete slab = EUR 12500.

2. House frame.

External walls of SIP panels 224mm (insulation 200mm, EPS80)

Roof covering 224mm (insulation 200mm, EPS80)

Price of the industrially produced set at the factory (without floor) = EUR 31200.

Assembly of the set on the site = EUR 6240.

3. Windows. (optional)

PVC windows, double-glazed windows = EUR 5900.

PVC windows, triple-glazed windows = EUR 6850.

Assembly of the windows on the site = EUR 860.

4. Terrace (heat-treated wood)

Terrace - heat-treated pine; terrace board 26x115 mm D30sg profile; Natur class (with branches) = EUR 1550.

Assembly of the terrace (heat-treated wood) on the site = EUR 1250.

5. Facade wall covering Heat-treated wood

Heat-treated pine; finishing board 22x140 mm C6 profile; Natur class (with branches) = EUR 6400.

Assembly of heat-treated pine; finishing board 22x140 mm C6 profile; Natur class (with branches) on the site = 4180 EUR.

6. Inner roof covering RUUKKI = EUR 2650.

Assembly of the roof RUUKKI on the site = EUR 2080.

7. Transport costs

Depending on the location of the site EUR 300-800.

The prices are given without interior decoration.

ALL PRICES ARE SPECIFIED EXCLUDING THE VAT.

The prices may change due to fluctuations in raw material prices.

CONTACT

“SIPpanel” Ltd.

Phone: +371 24115577

Email: sipmaja@sipmaja.lv

COMPANY DETAILS

“SIPpanel” Ltd.

VAT registration No.: LV41203070798

Address: 18-35 Zvejnieku Street, Roja, Roja county, LV-3264, Latvia

Address: 66C Augszemes Street, Akniste, Akniste county, LV-5208, Latvia