



6<sup>th</sup> house – 89.3m<sup>2</sup> + 41.9m<sup>2</sup> terrace.

1. Foundation. (optional)

Screw piles, SIP floor (SIP224) + terrace = EUR 8840.

Concrete strip foundation with subfloor = EUR 10500.

Insulated concrete slab = EUR 12400.

2. House frame.

External walls of SIP panels 224mm (insulation 200mm, EPS80)

Roof covering 224mm (insulation 200mm, EPS80)

Price of the industrially produced set at the factory (without floor) = EUR 19200.

Assembly of the set on the site = EUR 3850.

3. Windows. (optional)

PVC windows, double-glazed windows = EUR 5555.

PVC windows, triple-glazed windows = EUR 6450.

Assembly of the windows on the site = EUR 760.

4. Terrace (heat-treated wood)

Terrace - heat-treated pine; terrace board 26x115 mm D30sg profile; Natur class (with branches)  
= EUR 1660.

Assembly of the terrace (heat-treated wood) on the site = EUR 1250.

5. Roof covering, facade wall covering (metal RUUKKI)

RUUKKI Classic C 50Plus matt SR35-475C 0,50mm + gutters = EUR 6940.

Assembly of RUUKKI Classic C 50Plus matt SR35-475C 0,50mm + gutters on the site = EUR 6029.

6. Facade CEDRAL

Asbestos-free facade finishing plates, dimensions 60x30 cm, light grey CEDRAL = EUR 2810.

Assembly of the facade on the site = EUR 2222.

## 7. Transport costs

Depending on the location of the site EUR 300-800.

The prices are given without interior decoration.

ALL PRICES ARE SPECIFIED EXCLUDING THE VAT.

The prices may change due to fluctuations in raw material prices.

## CONTACT

“SIPpanel” Ltd.

Phone: +371 24115577

Email: sipmaja@sipmaja.lv

## COMPANY DETAILS

“SIPpanel” Ltd.

VAT registration No.: LV41203070798

Address: 18-35 Zvejnieku Street, Roja, Roja county, LV-3264, Latvia

Address: 66C Augszemes Street, Akniste, Akniste county, LV-5208, Latvia