



2nd house – 70.3m² + 34.3m² terrace.

1. Foundation. (optional)

Screw piles + SIP floor (SIP224) + terrace = EUR 9393.

Strip concrete foundation with subfloor = EUR 10500.

Insulated concrete slab = EUR 12400.

2. House frame.

External walls of SIP panels 224mm (insulation 200mm, EPS80)

Roof covering 224mm (insulation 200mm, EPS80)

Price of the industrially produced set at the factory (without floor) = EUR 20277.

Assembly of the set on the site = EUR 4400.

3. Windows. (optional)

PVC windows, double-glazed windows = EUR 3500.

PVC windows, triple-glazed windows = EUR 4240.

Assembly of the windows on the site = EUR 610.

4. Facade, terrace (heat-treated wood and ruukki)

Heat-treated pine; finishing board 20x140 mm C6 profile; Natur class (with branches) both for the facade and the ceiling = EUR 2275.

Terrace heat-treated pine; terrace board 26x115 mm D30sg profile; Natur class (with branches) = EUR 1405.

RUUKKI facade finish with “scale” = EUR 3270.

Assembly of the facade, terrace (heat-treated wood) on the site = EUR 2300.

Assembly of the facade (ruukki) assembly on the site = EUR 2280.

5. Roof covering

Roof internal construction, bitumen covering installed on a 5 degree slope = EUR 2630.

Roof inner gutter and external gutter with fasteners = EUR 450.

Assembly of the roof and gutters = EUR 2290.

6. Transport costs

Depending on the location of the site EUR 300-800.

The prices are given without interior decoration.

ALL PRICES ARE SPECIFIED EXCLUDING THE VAT.

The prices may change due to fluctuations in raw material prices.

CONTACT

“SIPpanel” Ltd.

Phone: +371 24115577

Email: sipmaja@sipmaja.lv

COMPANY DETAILS

“SIPpanel” Ltd.

VAT registration No.: LV41203070798

Address: 18-35 Zvejnieku Street, Roja, Roja county, LV-3264, Latvia

Address: 66C Augszemes Street, Akniste, Akniste county, LV-5208, Latvia