



3rd house - 105m² + 59m² terrace.

1. Foundation. (optional)

Screw piles, SIP floor (SIP224) + terrace = EUR 9820.

Strip concrete foundation with subfloor = EUR 10500.

Insulated concrete slab = EUR 12400.

2. House frame.

External walls of SIP panels 224mm (insulation 200mm, EPS80)

Roof covering 224mm (insulation 200mm, EPS80)

Price of the industrially produced set at the factory (without floor) = EUR 26225.

Assembly of the set on the site = EUR 5250.

3. Windows. (optional)

PVC windows, double-glazed windows = EUR 4750.

PVC windows, triple-glazed windows = EUR 5520.

Assembly of the windows on the site = EUR 760.

4. Facade, terrace (heat-treated wood)

Heat-treated pine; finishing board 20x140 mm C6 profile; Natur class (with branches) = EUR 3980.

Terrace heat-treated pine; terrace board 26x115 mm D30sg profile; Natur class (with branches) = EUR 2240.

Assembly of the facade and terrace (heat-treated wood) on the site = EUR 4800.

5. Roof covering

RUUKKI Classic C 50Plus matt SR35-475C 0.50mm RR23/dark grey + gutters = EUR 4450.

Assembly of RUUKKI Classic C 50Plus matt SR35-475C 0.50mm RR23/dark grey + gutters on the site = EUR 3970.

6. Transport costs

Depending on the location of the site EUR 300-800.

The prices are given without interior decoration.

ALL PRICES ARE SPECIFIED EXCLUDING THE VAT.

The prices may change due to fluctuations in raw material prices.

CONTACT

“SIPpanel” Ltd.

Phone: +371 24115577

Email: sipmaja@sipmaja.lv

COMPANY DETAILS

“SIPpanel” Ltd.

VAT registration No.: LV41203070798

Address: 18-35 Zvejnieku Street, Roja, Roja county, LV-3264, Latvia

Address: 66C Augszemes Street, Akniste, Akniste county, LV-5208, Latvia